



PLOT PLAN
SCALE: 1"=20'
LOT AREA= 14,500 ± SF



WINTHROP


AVENUE

BENCH MARK
TOP OF CONCRETE FOUNDATION
ELEV. = 20.00


NOTES

- NO WELLS WERE FOUND WITHIN 100' OF THE PROPOSED LEACHING PIT.
- EXISTING CESSPOOL TO BE ABANDONED, PUMPED AND FILLED WITH CLEAN SAND.
- INSTALLER SHALL ASCERTAIN LOCATIONS OF EXISTING UNDERGROUND UTILITIES PRIOR TO EXCAVATION.


PROFILE OF SYSTEM



PLAN VIEW OF SYSTEM



TYPICAL LEACHING PIT CROSS-SECTION



SCHEDULE OF ELEVATIONS

	FINISHED GRADE ABOVE STRUCTURE	FINISHED GRADE ABOVE STRUCTURE
Top of foundation	= 20.00	
Basement floor	= N/A	
Invert of pipe at foundation	= EXISTING 19.1	
Invert at septic tank inlet	= 17.00	
Invert at septic tank outlet	= 16.75	19.1
Invert at distribution box inlet	= N/A	
Invert at distribution box outlet	= N/A	19.1
Invert at leaching pit inlet	= 16.50	19.1
Elevation of leaching pit bottom	= 10.50	
Finished grade over leaching pit - See Plot Plan		

NOTE
NO GROUNDWATER WAS ENCOUNTERED AT EL. = 4.6 ON SEPTEMBER 30, 1991.

SOIL TEST DATA

DEEP TEST PIT 1 (SURFACE ELEVATION 19.1)		DEEP TEST PIT 2 (SURFACE ELEVATION 19.1)		PERCOLATION TEST DATA			
DATE OF TEST	SOIL DESCRIPTION	DATE OF TEST	SOIL DESCRIPTION	TEST PIT NO.	DATE	TOP OF 12" OF WATER	RATE MINUTES PER INCH
0'-0"	TOPSOIL			#1	9/30/91	48"	15"
6'-24"	SILTY SAND SUBSOIL						
24'-72"	COARSE SAND						
72'-174"	MEDIUM SAND						
GROUND WATER WAS ENCOUNTERED AT A DEPTH OF 4.6 (ELEVATION 4.6)		GROUND WATER WAS ENCOUNTERED AT A DEPTH OF (ELEVATION)		DEEP TEST PIT 3 (SURFACE ELEVATION)			
DATE OF TEST	SOIL DESCRIPTION	DATE OF TEST	SOIL DESCRIPTION	DATE OF TEST	SOIL DESCRIPTION	DATE OF TEST	SOIL DESCRIPTION
GROUND WATER WAS ENCOUNTERED AT A DEPTH OF (ELEVATION)		GROUND WATER WAS ENCOUNTERED AT A DEPTH OF (ELEVATION)		GROUND WATER WAS ENCOUNTERED AT A DEPTH OF (ELEVATION)			

GENERAL NOTES

- Elevations refer to APPROXIMATE MEAN SEA LEVEL DATUM. See Bench Mark on Plot Plan located ON TOP OF CONCRETE FOUNDATION.
- Finished grading to be done in accordance with plot plan.
- Percolation tests performed in accordance with the instructions in Title 5 of the Massachusetts State Environmental Code.
- All construction to conform to Title 5 of the Massachusetts State Environmental Code, and the Board of Health requirements for the Town of OAK BLUFFS.
- All topsoil, subsoil and deleterious material, if any, must be excavated and removed below the leaching pit and to a distance of 10 feet from all sides of the leaching pit. Excavate down to 12 inches below the surface of the natural permeable soil. Backfill as required with a clean gravel or sandfill material, free from fines, clay, organic matter, and large boulders, having a percolation rate in its original location and after placement of 2 minutes per inch or faster. Construct pit in this material.
- All washed stone in the leaching field must have less than 0.2 percent material finer than a number 200 sieve as determined by the A.A.S.H.O. Test Methods T-11 and T-27 (latest edition).
- Tight joint piping to consist of Polyvinyl Chloride Pipe (PVC), Schedule 40, unless otherwise noted.
- In cases where ledge or boulders are present, Schofield Brothers, Inc. will not be responsible for assuring the amount of rock to be encountered.
- Schofield Brothers, Inc. will not be responsible for the performance of this system unless constructed as shown. Any alterations must be approved in writing by Schofield Brothers, Inc.
- Heavy machinery shall not be permitted to pass over the leaching pit.
- The Board of Health shall require inspection of all construction by the design engineer or by an agent of the Board of Health, and require such person to certify in writing that all work has been completed in accordance with the terms of the permit and the approved plans.
- No permanent structure may be constructed over the 100% expansion area.
- For proper performance, septic tank should be inspected at least once a year and when the total depth of scum and solids exceeds 1/2 the liquid depth of the tank, the tank should be pumped.

DESIGN DATA

- Estimated Hydraulic Loading: ONE Bedrooms at 110 gallons per day per bedroom = 110 GPD. Garbage disposal is NOT allowed with this design.
- Septic Tank Size: Average daily flow = 110 GPD X 1.50 = 165 gallons (minimum). Septic tank provided = 165 gallons.
- Design percolation rate: 1.00 MPT. Side wall loading = 1.00 gallons / S.F. Bottom loading = 1.00 gallons / S.F.
- Leaching Area: Total side wall area provided = 160 S.F. X 2.50 gal / S.F. = 400 gal. Total bottom area provided = 56 S.F. X 1.00 gal / S.F. = 56 gal. Maximum allowable loading (under Title 5) = 456 gallons. Actual hydraulic loading = 110 gallons. Minimum size leaching area allowed under the Town of OAK BLUFFS Board of Health requirements is 25% IN EXCESS OF TITLE 5 FOR PARCELS OUTSIDE THE WATERCOURSE DISTRICT.

LEGEND

- XX— Denotes proposed contour
- FG = XX X Denotes proposed finished grade
- XX-- Denotes existing contour
- XX.X Denotes existing spot elevation
- Denotes test hole location
- PVC Denotes polyvinyl chloride pipe (see Note #7 above)
- V.C.B. & S. Denotes vitrified clay bell and spigot
- E.H.C.I. Denotes extra heavy cast iron
- W— Denotes water service
- R— Denotes approximate property line
- O.W.— Denotes overhead wires
- D— Denotes storm drain pipe
- Denotes catch basin

PROPOSED SEWAGE DISPOSAL SYSTEM

TO REPLACE A FAILED SYSTEM SERVING AN EXISTING ONE BEDROOM DWELLING WINTHROP AVENUE ASSE. P.L. 17-10 OAK BLUFFS, MASS.

APPLICANT: BETTY SULLIVAN
40 CAROL STREET, WINTHROP
P.O. BOX 2226
OAK BLUFFS, MA. 02557

TEL. NO. 693-1737

DATE: OCTOBER 4, 1991 SCALE: AS NOTED

DESIGNED BY: DSH DRAWN BY: DSH CHECKED BY: DSH

SCHOFIELD BROS. & SONS, INC.
P.O. BOX 334 VINEYARD HAVEN, MA. 02566